FALIZ
PAJOUHESH PARS CO.

FALIZ PAJOUHESH PARS CO.



F4.B

TRAILER MOUNTED COILED TUBING UNIT

The Coiled Tubing Unit (CTU) is a self-contained, trailer-mounted system for live-well intervention, integrating an injector head, tubing reel, pressure-control stack and control cabin to safely run and retrieve coiled tubing under wellbore pressure.

Rated for high-pressure well control, the unit is configured for a range of coiled tubing sizes and intervention duties, from land rigs to offshore platforms.

80K Injector Head

* 80,000 lb continuous pull
* 100,000 lb intermittent pull force
* At 40,000 lb continuous pull, capable of 200’ per minute
* Capable of 40,000 lb of snub force
* Runs pipe sizes from 1-1/4" up to 2-3/8" OD coiled tubing

Reel Capacity and Specs

* 15,000 working PSI rotating joint
* 48,000 ft of 1-1/4"
* 24,000 ft of 1-3/4"
* 18,000 ft of 2"

Stripper Assembly

* Dual pack off
* 15,000 lb working PSI
* 4-1/16", 15K flange
* Side door for easy access with tubing deployed

4-1/16" Quad B.O.P.

* 15,000 lb working PSI
* Runs 1-1/4" to 2" tubing

Flow Cross

* 15,000 lb working pressure

Single BOP

* 1-1/4" to 2" coiled tubing
* 15,000 lb working pressure

Control Cabin

* Data acquisition system
* Continuous monitoring of job parameters
* Real-time modeling and fatigue software

Wet Kit

* 5,000 PSI wet kit

No.721, phase 2, Industrial zone 2 Andimeshk Road, Ahvaz, Khuzestan
www.falizgroup.com info@falizgroup.com
061-33739164-7 061-33739163 09163001892-09168089194